



* Information provided by the power company

FEEDER SCHEDULE

- ⚠ 2000A Secondary - (5) 4" pvc w/(4) 600 thwn
- ⚠ 150A - 1-1/2" c w/(4) 1/0 thwn
- ⚠ 150A - 2" c w/(4) 2/0 thwn
- ⚠ 200A - 2" c w/(4) 3/0 thwn
- ⚠ 300A - 2-1/2" c w/(3) 300 thwn
- ⚠ 800A - (3) Sets 2-1/2" c w/(4) 250 thwn
- ⚠ 800A - (3) Sets 2-1/2" c w/(4) 300 thwn

| TRANSFORMER FEEDER SCHEDULE - 480V > 120/208V 3-phase | | | |
|---|---------------------------|--------------------------------|------|
| | PRIMARY | SECONDARY | |
| 15kVA | ⚠ 1/2" c w/ (3) #10, #10g | ⚠ 3/4" c w(4) #6 thwn, #8g | 60A |
| 30kVA | ⚠ 3/4" c w/ (3) #8, #10g | ⚠ 1-1/4" c w(4) #3 thwn, #8g | 100A |
| 45kVA | ⚠ 1" c w/(3) #4, #8g | ⚠ 1-1/2" c w/(4) 1/0 thwn, #6g | 150A |
| 75kVA | ⚠ 1" c w/(3) #3, #8g | ⚠ 2" c w/(4) 4/0 thwn, #2g | 225A |

SEAL

12/9/2008

MULTI-TENANT INVENTORY AND DISTRIBUTION CENTER FOR

ARLINGTON COMMERCE CENTER

VISTAR

4905 NEW YORK AVE.
 ARLINGTON, TEXAS
 76018

General Contractor:
 KBD CONSTRUCTION SERVICES
 1431 Greenway, Suite 740
 Irving, Texas 75038

Architect:
 MACGREGOR ASSOCIATES
 ARCHITECTS
 2830 Paces Ferry Rd. NW, Suite 500
 Atlanta, Georgia 30339

MULTI-TENANT INVENTORY AND DISTRIBUTION CENTER FOR

SHEET TITLE
RISER DIAGRAM

SHEET NUMBER
E7